

ABSTRACT OF COST/BILL OF QUANTITY OF SHELTER HOME					
S.No	Description	Unit	Estimated Quantity	Rate	Total Amout
1	Earth excavation undressed upto single throw of kassi phaorah or shovel etc : in ashes, sand, soft soil or silt clearance	CFT	349.18		
2	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	CFT	45.38		
3	Overburnt brick work in foundation upto 10 ft. height : Cement, sand mortar 1:6	CFT	204.19		
4	1st class brick work other than building upto 10 ft. height : Cement, sand mortar 1:4	CFT	749.25		
5	Cement plaster 1:4 upto 20' height 1/2" thick	SFT	2294.00		
6	Damp proof course of cem. conc. 1:2:4 including bitumen coat, 1 layer polythene & 1 coat bitumen (2" thick)	SFT	86.25		
7	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	CFT	203.28		
8	Providing and fixing steel gate of 16-18 SWG MS Sheet Gate with angle iron frame (2"x2"x3/16") with side window, lock, painting	SFT	91.50		
9	Distempering New surface : Three coats	SFT	1529.00		
10	Preparing surface & painting with snowcem / weathershield paint : two coats	SFT	716.00		
11	Providing and Laying Prestressed Roof of Slab/Girder, 2" thick PCC 1:2:4 with chicken mesh, polythene, mud, tar	SFT	572.00		
12	Septic Tank (int.Size: 7'x2'x5') and sockage pit with 3' dia complete	No.	1.00		
13	Supply and Laying of RC hume pipes in position including jointing 30" dia in sockage pit	RFT	8.00		
14	Supplying and Fixing Polyethylene Water Tank made from food grade FDA Certified raw material, 3 layers UV stablized, inert	Each	1.00		
15	Providing, laying cutting, jointing, testing PPRC pipeline in walls/trenches with pipes (confirming to DIN 8077/8078, PN 20	RFT	40.00		
16	Providing, laying cutting, jointing, testing PPRC pipeline in walls/trenches with pipes (confirming to DIN 8077/8078, PN 20	RFT	20.00		
17	Providing and Fixing brass ball float valve of approved quality: 3/4" dia	Each	1.00		
18	Providing and Fixing glazed earthen ware WC squatting type with built-in foot rests complete in all respects : Coloured	Each	1.00		
19	Providing and fixing chromium plated (CP) bib-cock heavy duty of approved quality : 2 cm 3/4"	Each	3.00		

20	Providing and Fixing 'P' trap of approved quality including GI grating & PCC chamber 4" (100 mm) glazed	Each	1.00		
21	Providing and Fixing of pipe type B nikasi system including testing in all respect 110 mm	RFT	13.00		
22	Supply and fixing of 0.5 HP Monoblock water pump 1.25"x1" single phase upto 72 ft head (Type SE) i/c all accessories	Each	1.00		
23	Supply and Fixing of CP floor Truff Jalli with Grating 6"×6" complete	Each	2.00		
24	Supplying and Fixing UPVC soil waste and vent pipe class B : 4" dia	RFT	15.00		
25	Supply and Erection circuit breaker (imported) on sahl wood board complete : 20/25/30 Amp.	Each	2.00		
26	Wiring overhead line in 2 single core, PVC insulated cable with GI wire #8 SWG : 3/0.029"	Bndl	1.00		
27	Wiring overhead line in 2 single core, PVC insulated cable with GI wire #8 SWG : 7/0.029"	Bndl	0.50		
28	Light bulb	Each	4.00		
29	Button/switches for bulb etc.	Each	8.00		
30	Donor Plaque	Each	1.00		
Total Cost					